

OFFICE OF THE PRINCIPAL, RAJDHANI COLLEGE, BHUBANESWAR.


No. 2104

Dt. 25/8/16

QUOTATION CALL NOTICE

Sealed quotations are invited in plain paper from interested Firms/Dealers/Furniture makers having up to date TIN clearance to supply Computers, Inverter, Computer Chair, Air Conditioner, Making of Work Station for Computer Lab, LAN and electrical works in the I.T. Lab of College. For Details visit: www.rajdhanicollege.org.in

The specifications of the items are provided in the separate sheet enclosed. The quotations should reach the undersigned by 3 pm of 06.09.2016(Tuesday), positively. In all matters the decision of the undersigned is final and reserves the cancellation of process without assigning reason there to.



Principal

Rajdhani College, Bhubaneswar.

Memo No.

Dt.

Copy to the OIC, Website for hoisting this advertisement/ B. Das, D.A.,I.T. for information and necessary action.


Principal

Rajdhani College, Bhubaneswar.

Specification List for I.T.Lab

N.B: The rates should be quoted in separate sheets item wise clearly

All items should be installed in the I.T. Lab., so prices should be with installation cost

1. Computer: Intel Core i3 (3.6GHz/3MB Cache), 500GB SATA HDD 7200rpm, 4GB DDR3 RAM, Genuine Windows 8.1 preloaded OS, 19" HD LED Monitor, Key Board, Mouse, DVD RW. 3 years Onsite full warranty. (HP/Dell or equivalent)
2. (a) The workstation arrangement for the computers be made with following specification:
Supply & fitting of Furniture for Computer Lab Work Station with 19 mm **water proof, termite proof ply** (reputed brand like Green Ply / Century Ply), pasted with 1mm laminate (reputed brand like Merino, Century), 21" width, 30" + 15" height, 12mm Opaque light green Glass partition, CPU chamber with door, Sliding K B tray, Foot rest, Cable manager etc. (Rate per running foot) For 16-18 students
(b) The work station for teacher: Same material without 15" elevation and glass partition for teacher table of 'L' shape and arrangement of keeping computer, CPU chamber with door, Sliding K B tray, Foot rest, Cable manager etc.(per running foot rate)
3. Networking and electric cabling be made with following specifications: Supply & fitting of D-Link Cat 6 Cable with casing & Single IO Box with Keystone inside the computer Lab Work station. 1.5 mm Copper wire (Finolex) & 2 Nos of 6 amp 3 Pin Sockets & 2 nos of 6 amp switches (Anchor/Cona) per Computer point.
4. Air Conditioners with electrifications and fittings will be made with following specification: 1.5 Ton 5 star Split AC , R410A refrigerant, wall mountable 5KVA stabilizer (V guard or equivalent 90V to 270 V) with Installation and wiring from main switch with 6 mm copper wire & 32amp MCB (Finolex or equivalent) LG/Hitachi or equivalent.
5. Inverter 3.6KVA, 12V, 150 Tubular battery (4 nos) with trolley and fitting in the laboratory
6. Revolving Computer Chiars with wheels, low back and good quality cushion

Tepu
25/8/16.